# INSULATION ADDENDUM

by William

80 Lamb Ave, Toronto | North Arrow Limited | Framing package

Quantities for the insulation, added to the framing order. Wall types from the wall schedule on A004. Square feet are wall face area with window and door openings deducted; the order column adds waste and rounds up. Pricing to follow with the yard quote.

### EXTERIOR MINERAL WOOL, 3" (75 MM) PINNED SEMI-RIGID, R12ci (W1 AND W2 PARAPETS)

| ELEVATION | PHASE 1 SQ FT | PHASE 2 SQ FT | NET SQ FT | ORDER SQ FT +10% | BOARDS 2'x4' |
|---|---|---|---|---|---|
| North | 220 | 498 | 718 | 790 | 99 |
| South | 220 | 370 | 590 | 650 | 82 |
| East | 65 | 156 | 221 | 245 | 31 |
| Stair enclosure, south faces above the roof | | 111 | 111 | 125 | 16 |
| Stair enclosure, west face above the roof | | 26 | 26 | 30 | 4 |
| **Total 3"** | **505** | **1,162** | **1,667** | **1,840** | **232** |

### EXTERIOR MINERAL WOOL, 5" (125 MM) STICK-PINNED SEMI-RIGID (W1a, WEST WALL)

| AREA | PHASE 1 SQ FT | PHASE 2 SQ FT | NET SQ FT | ORDER SQ FT +10% | BOARDS 2'x4' |
|---|---|---|---|---|---|
| West: the two infill panels beside the curtain wall, and the band up to the parapet top | 46 | 91 | 138 | **155** | **20** |

### INTERIOR BATTS, R19 MINERAL FIBRE, 140 MM (5 1/2"), 2x6 STUDS AT 16" (W1)

| PHASE | WHAT IS IN IT | NET SQ FT | ORDER SQ FT +5% | |
|---|---|---|---|---|
| **Phase 1** | 1st floor exterior walls, from the top of the curb | 474 | 500 | |
| **Phase 2** | 2nd floor exterior walls and the stair enclosure walls | 978 | 1,030 | |
| **Total** | | **1,452** | **1,530** | |

### HOW IT WAS MEASURED

- Exterior mineral wool runs continuous over the DensGlass from the top of the concrete curb to the top of the parapets and the stair enclosure roof, including the floor and roof bands and the parapet faces.
- Phase 1 is the curb up to the top of the 2nd floor subfloor; Phase 2 is everything above, the same split as the framing order.
- Batts fill the stud cavities of the exterior walls only; bag count depends on the brand bought (R19 to suit 2x6 at 16").
- Boards counted as 2' x 4' (8 sq ft). Adjust if the yard stocks another size.

### NOT INCLUDED / TO CONFIRM

- Thickness: the wall schedule on A004 says 75 mm (3"); a detail in the set notes 4" exterior Rockwool. Quantities are at 75 mm. Marek to confirm with Kunaal.
- Insulation pins, washers and fasteners for the mineral wool: to be added with the product chosen.
- Parapet cavities, floor and roof assembly insulation (R32 mineral wool), and sound batts in interior partitions.
- DensGlass at the floor and roof bands: the framing order carries DensGlass on the stud walls only. Extra sheets for the bands will be added in the next issue of the order summaries.

**ISSUED FOR BUDGET AND COORDINATION, 23 OCT 2026**

80 Lamb Ave – Laneway House
Oct 23, 2026

**Insulation Addendum – T 1.07-IA**