ORDER SUMMARY AND BUDGET

Lamb Laneway House and Secondary Suite | 80 Lamb Ave, Toronto, Ontario | North Arrow Limited | Framing package

by William

One line per product the yard stocks, with the batch split so Marek can call off the delivery per floor. Prices: quote = Downtown Lumber 1 May 2026; est. = estimated price pending re-quote. Five months old and lumber has moved: treat the budget as an order of magnitude until Downtown Lumber re-prices this list.

ORDER SUMMARY BY PRODUCT

PRODUCT	B1 GF WALLS	B2 DECK	B2B BALCONY	B3 2F WALLS	B4 ROOFS	SITE, FAST.	TOTAL	UNIT	UNIT PRICE	SRC	EXT. BEFORE HST
2x6 x 12'	59	3	9	74	18		**163**	pcs	$11.49	est.	$1,872.87
2x6 x 16'	24		2	24	31		**81**	pcs	$14.99	est.	$1,214.19
DensGlass 5/8" gypsum sheathing 4x8 x 4x8	21			30	16		**67**	pcs	$44.00	est.	$2,948.00
1x3 SPF horizontal furring @ 16" (drainage holes drilled) x 1x3 x 8'	58			78	41		**177**	pcs	$2.49	est.	$440.73
2x6 x 10'	5			7	7		**19**	pcs	$9.49	est.	$180.31
2x6 x 8'	9	4		3	30		**46**	pcs	$7.49	est.	$344.54
2x8 x 10'	2			1	16		**19**	pcs	$18.98	quote	$360.62
2x8 x 8'	3			4			**7**	pcs	$15.49	est.	$108.43
2x6 x 104 5/8" precut	29			2			**31**	pcs	$6.25	quote	$193.75
2x4 x 104 5/8" precut	45						**45**	pcs	$4.49	quote	$202.05
2x4 x 16'	11			7	9	24	**51**	pcs	$8.99	quote	$458.49
2x4 x 12'	6			5			**11**	pcs	$7.49	est.	$82.39
1/2" plywood x 4x8	30			15			**45**	pcs	$31.99	quote	$1,439.55
2x4 x 92 5/8" precut	14			52			**66**	pcs	$3.99	est.	$263.34
2x4 x 8'	3			1			**4**	pcs	$4.49	est.	$17.96
2x4 x 10'	5			1			**6**	pcs	$5.99	est.	$35.94
2x6 x 92 5/8" precut				53	34		**87**	pcs	$6.49	quote	$564.63
2x6 x 14'				7	10		**17**	pcs	$9.89	quote	$168.13
3/4" exterior-grade plywood x 4x8					11		**11**	pcs	$52.99	est.	$582.89
2x10 x 8'					11		**11**	pcs	$18.99	est.	$208.89
2x10 x 12'					5		**5**	pcs	$27.98	quote	$139.90
1 1/2 x 5 1/2 LSL x 12'	2						**2**	pcs	$59.40	est.	$118.80
1 1/2 x 5 1/2 LSL x 10'	2						**2**	pcs	$49.50	est.	$99.00
1/2" through-bolts with nut and washer, LSL nailer to the column flange	34						**34**	bolts	$2.75	est.	$93.50
Gasket between the LSL nailer and the steel column flange, full height both columns (foam sill gasket 5 1/2" x 82' or a Blueskin SA strip)	1						**1**	roll	$19.99	quote	$19.99
TEK #12 x 2 3/4" self-drilling screws, 100/box, 2x10 nailer to the W200x36 beam and outriggers		2					**2**	boxes	$34.00	est.	$68.00
1/2" through-bolts with nut and washer, 2x10 nailer to the W200x36 beam and outrigger flanges		50					**50**	bolts	$2.75	est.	$137.50
2x10 x 16'		4			2		**6**	pcs	$37.99	est.	$227.94
TJI 360 9 1/2" x 16'		29			10		**39**	pcs	$55.20	est.	$2,152.80
3/4" T&G plywood subfloor 4x8 x 4x8		19			4		**23**	pcs	$49.99	quote	$1,149.77
PL400 subfloor adhesive 828 mL		14			3		**17**	tubes	$13.99	est.	$237.83
1/2" plywood deck sheathing 4x8 (F4: 13 mm plywood under the 2-ply membrane) x 4x8			4				**4**	pcs	$31.99	quote	$127.96
2x4 PT x 12'			7				**7**	pcs	$9.99	est.	$69.93
5/4 x 6 cedar decking x 8'			29				**29**	pcs	$21.00	est.	$609.00
Stainless deck screws #8 x 2 1/2", 350/box			2				**2**	boxes	$42.00	est.	$84.00
Metal railing brackets and the white oak guardrail (A405 detail 1)			0				**0**		to quote	to quote	

ISSUED FOR BUDGET AND COORDINATION, 23 OCT 2026

80 Lamb Ave – Laneway House
Oct 23, 2026

Order Summary – T 1.07

ORDER SUMMARY AND BUDGET

Lamb Laneway House and Secondary Suite | 80 Lamb Ave, Toronto, Ontario | North Arrow Limited | Framing package

by William

PRODUCT	B1 GF WALLS	B2 DECK	B2B BALCONY	B3 2F WALLS	B4 ROOFS	SITE, FAST.	TOTAL	UNIT	UNIT PRICE	SRC	EXT. BEFORE HST
7/8" roof sheathing board 4x8 (A004: 22 mm) x 4x8					14		**14**	pcs	$58.00	est.	$812.00
Simpson LUS210 joist hangers					22		**22**	pcs	$2.10	est.	$46.20
Simpson LUS26 joist hangers					14		**14**	pcs	$1.95	est.	$27.30
2x10 x 10'				4	25		**29**	pcs	$24.49	quote	$710.21
2x8 x 12'					2		**2**	pcs	$22.99	quote	$45.98
1 3/4 x 7 1/4 LVL x 20'					4		**4**	pcs	$100.60	est.	$402.40
1/2" plywood over the purlins x 4x8					7		**7**	pcs	$31.99	quote	$223.93
5/8" roof sheathing board 4x8 on the rafters x 4x8					7		**7**	pcs	$42.00	est.	$294.00
LVL 1 3/4 x 11 1/4 x 14'				3			**3**	pcs	$111.30	est.	$333.90
5/8" plywood sub-treads and risers (A404 det 1: 5/8" plywood subfloor typical for all treads) x 4x8				3			**3**	pcs	$42.00	est.	$126.00
2x4 PT x 2x4 x 8' PT				1			**1**	pcs	$6.49	est.	$6.49
LVL 1 3/4 x 11 1/4 x 8'					2		**2**	pcs	$63.60	est.	$127.20
5/8" plywood sub-treads and risers x 4x8					2		**2**	pcs	$42.00	est.	$84.00
7/8 ply x 7/8 4x8		1					**1**	pcs	$58.00	est.	$58.00
1 1/4 x 9 1/2 LSL x 12'		9					**9**	pcs	$79.08	est.	$711.72
1 3/4 x 9 1/2 Microllam x 16'		6			7		**13**	pcs	$105.44	quote	$1,370.72
1 3/4 x 9 1/2 Microllam x 12'		3			2		**5**	pcs	$79.08	quote	$395.40
1 3/4 x 9 1/2 Microllam x 18'			3		7		**10**	pcs	$118.62	quote	$1,186.20
1 1/4 x 9 1/2 x 12' x 12'		3					**3**	pcs	$79.08	est.	$237.24
Plate washers 3" x 3" x 1/4"	26						**26**	pcs	$1.40	est.	$36.40
Simpson HGUS5.50/10 (3-ply LVL hanger)		2					**2**	pcs	$27.99	quote	$55.98
Simpson LSC adjustable stringer connectors				6			**6**	pcs	$9.50	est.	$57.00
Simpson LUS210 hangers at the winder carriages					6		**6**	pcs	$2.10	est.	$12.60
Simpson IUS2.56/9.5 (TJI face-mount hanger)		14					**14**	pcs	$6.25	est.	$87.50
Simpson H2.5A hurricane ties		8			70		**78**	pcs	$1.25	est.	$97.50
Simpson LUS26 (2x6 hanger)			26				**26**	pcs	$1.95	est.	$50.70
Simpson A35 framing angles					48		**48**	pcs	$1.35	est.	$64.80
Simpson LSTA24 straps					12		**12**	pcs	$4.50	est.	$54.00
Simpson HUS410 (B10-2 end)					2		**2**	pcs	$24.99	est.	$49.98
2x10 x 14'					4		**4**	pcs	$32.99	est.	$131.96
Simpson HUS210-2 hangers					11		**11**	pcs	$14.50	est.	$159.50
Simpson LSSU210 hangers					12		**12**	pcs	$9.95	est.	$119.40
Simpson LUS210 hangers					16		**16**	pcs	$2.10	est.	$33.60
3 1/4" x 0.131 strip framing nails (30 deg paper tape), 4000/box						5	**5**	boxes	$72.00	est.	$360.00
2 3/8" x 0.113 ring-shank strip nails, 5000/box						2	**2**	boxes	$68.00	est.	$136.00
1 1/2" x 0.148 joist hanger nails (10d), 5 lb box						7	**7**	boxes	$28.00	est.	$196.00
Simpson SDS 1/4" x 3" structural screws, 50/box						2	**2**	boxes	$45.00	est.	$90.00
DensGlass screws #8 x 1 5/8" corrosion-resistant, 1000/box						5	**5**	boxes	$58.00	est.	$290.00
Subfloor screws #8 x 2" (square drive), 2000/pail						2	**2**	pails	$75.00	est.	$150.00
Tapcon 1/4" x 3 1/4" concrete screws, 50/box						2	**2**	boxes	$38.00	est.	$76.00
Blueskin SA 12" x 75' self-adhered membrane over the curb top, lapped down the outside	2						**2**	rolls	$135.00	est.	$270.00

ISSUED FOR BUDGET AND COORDINATION, 23 OCT 2026

80 Lamb Ave – Laneway House
Oct 23, 2026

Order Summary – T 1.07

ORDER SUMMARY AND BUDGET

Lamb Laneway House and Secondary Suite | 80 Lamb Ave, Toronto, Ontario | North Arrow Limited | Framing package

by William

PRODUCT	B1 GF WALLS	B2 DECK	B2B BALCONY	B3 2F WALLS	B4 ROOFS	SITE, FAST.	TOTAL	UNIT	UNIT PRICE	SRC	EXT. BEFORE HST
Blueskin primer (Blue Prep or Aquatac), 3.78 L	2						**2**	pails	$78.00	est.	$156.00
Sill gasket 5 1/2" x 82' foam	2						**2**	rolls	$19.99	quote	$39.98
2x12 PT x 16'	2						**2**	pcs	$54.99	est.	$109.98
Blueskin SA 6" x 75' (window sills, jambs, head laps)						1	**1**	rolls	$72.00	est.	$72.00
Blueskin SA 6" x 75' round the skylight W12 curb: up the curb faces and lapped 6" onto the roof board					1		**1**	roll	$72.00	est.	$72.00
Tuck Tape (red sheathing tape) 60 mm x 66 m						8	**8**	rolls	$17.99	est.	$143.92
Weather-resistant air barrier: Adhero 3000 self-adhered 4' x 100' (as specified, A004 W1)						5	**5**	rolls	$420.00	est.	$2,100.00
6 mil poly 12' x 300' (slab vapour barrier is Stego 15 mil, separate)						1	**1**	roll	$34.99	quote	$34.99
1x4 x 12' let-in style diagonal braces and string-line stakes						30	**30**	pcs	$4.99	est.	$149.70
1/2" plywood 4x8 for guards, ramps and the stair opening cover						4	**4**	sheets	$31.99	quote	$127.96
7 1/4" 24T framing blades						6	**6**	pcs	$18.00	est.	$108.00
7 1/4" PCD fibre-cement/gypsum blade (DensGlass cutting) and utility knife blades 100-pack (score and snap)						1	**1**	each	$65.00	est.	$65.00
Utility knife blades, 100-pack						2	**2**	packs	$24.00	est.	$48.00
Reciprocating saw blades, wood with nails, 10-pack						2	**2**	packs	$29.00	est.	$58.00
FRAMING PACKAGE BEFORE HST											**$30,087**

ESTIMATED BUDGET

order of magnitude at five-month-old pricing; the yard re-prices the order summary above

	AMOUNT
Lines priced from the 1 May quote	$9,016
Lines priced at estimated prices (re-quote)	$21,071
Lines with no price (to quote)	1 lines, not in the total
Framing package before HST	$30,087
HST 13%	$3,911
Framing package including HST	$33,998
By batch, before HST	B1 $4,835 | B2 $5,199 | B2B $1,431 | B3 $4,739 | B4 $9,462 | site and fasteners $4,421
For comparison: Downtown Lumber quote 3027967, 1 May 2026, earlier design, scan cut off at the lower roof	$19,136.71 + HST = $21,624.48

OPTION: TIMBERSTRAND LSL 1 1/2" X 5 1/2" FOR EVERY 2X6 STUD

Straight, no crown, no twist; what the builder asked about for warp restraint on the 10'-7" walls. Same cut lengths as the SPF list. LSL comes 8', 9', 10', 12', 14', 16' and 20'; order the same stock mix as the SPF studs. Plates stay SPF (or LSL for the 16' top plates on the long walls). Price to quote; budget at about $4.95/LF est.

Total LSL stud length if every 2x6 stud is swapped	1,935 LF
Budget for the LSL at the estimate rate, against the SPF stud lines it replaces	$9,579 before HST, to quote
Where it matters most	The 10'-7" west-zone walls and the parapets, where a twisted stud shows through the corrugated metal. A middle path is LSL on those two groups only.
What stays SPF	Plates, blocking, cripples, headers, interior partitions.

ISSUED FOR BUDGET AND COORDINATION, 23 OCT 2026

80 Lamb Ave – Laneway House
Oct 23, 2026

Order Summary – T 1.07